

PLANNING BOARD MEETING

Lincoln Community Center

February 25, 2025



AGENDA


- Existing Conditions:
Buildings, Landscape, Civil
- Proposed Site Plan:
Site Circulation + Exterior Spaces
- Civil Engineering:
Zoning, Parking, Stormwater, ConCom
- Building Performance
Materials, Energy Efficiency, Dark Skies
- Discussion




EXISTING CONDITIONS: BUILDINGS



EXISTING CONDITIONS: LANDSCAPE





DRAWN BY: AM

SITE PLAN: EXTERIOR FEATURES



- 1 Proposed Building
FFE 218.5
- 2 Multi-Use Court
- 3 Patio
- 4 Open lawn
- 5 Play structures
- 6 Emergency Vehicular
access
- 7 Rain garden (add alternate)
- 8 Screen planting
- 9 Existing vegetation to
remain
- 10 Boardwalk crossing
- 11 Utility area
- 12 Leaching Field
- Approx Limit of Work



WEST PATIO | MAIN ENTRANCE

3 7



EAST PATIO 3



NORTH PATIO

3

4



PEDESTRIAN BRIDGE 8 9 10



EAST PLAY SPACE

2 4 5

CIVIL ENGINEERING: ZONING

ZONING / PARKING REQUIREMENT CALCULATIONS

ZONING DISTRICT RESIDENTIAL ONE (R-1) BUILDING AND LOT COMPLIANCE	REQUIRED	EXISTING	PROPOSED
MINIMUM LOT AREA (SF)	1991730±	2,368,009	2,368,009
MINIMUM OPEN LAND (SF)	-	-	-
MAXIMUM BUILDING HEIGHT (STORIES)	2.5	1	1
MAXIMUM BUILDING HEIGHT (FT)	36	15.0	15.0
MINIMUM LOT FRONTAGE (FT)	120	970.6	970.6
MINIMUM LOT WIDTH (FT)	250	1103±	1103±
MINIMUM FRONT YARD (FT)	75	100.6	100.6
MINIMUM REAR & SIDE YARD (FT)	75	117.3	124.4
MAXIMUM GROSS FLOOR AREA (SF)	-	194,459	199173
MAXIMUM GROSS FLOOR AREA TO BUILDINGS DEVELOPED SITE	-	27,780	39835
MAXIMUM NUMBER OF DWELLING UNITS	-	-	-
MAXIMUM RATIO OF THE AREA OF OCCUPIED BY IMPERVIOUS SURFACE ON THE SITE TO DEVELOPABLE SITE AREA	-	39%	40%

OFF-STREET ACCESSORY PARKING BYLAW REQUIREMENTS (Sec 15.3.2.1, Subsections b and c)	REQUIRED
Community Center (Subsection b) = 244 occupants @ 1 space / 3 occupants	82
Hartwell Building (Subsection c) School Administration = 19 employees @ 1 space / 2 employees	10
Hartwell Building (Subsection c) Magic Garden Preschool = 4 classrooms @ 1 space / classroom + 2 non teachers @ 1 space/non-teacher	6
Total Required spaces	98

EXISTING AND PROPOSED PARKING SPACES	EXISTING	PROPOSED
<i>Section 15.3.2 allows the use of parking within 600 feet of the building. This includes Ballfield Rd, Tennis Courts, and extra Brooks Lot spaces.</i>		
HARTWELL LOT (TO BE RENOVATED)	55	54
BALLFIELD ROAD SPACES (TO REMAIN)	6	6
SOUTH (TENNIS COURT) SPACES (TO REMAIN)	16	16
BROOKS / POOL LOT(TO REMAIN)	57	57
TOTAL	134	133

OFF-STREET ACCESSORY PARKING DIMENSIONS FOR PROPOSED HARTWELL LOT	REQUIRED	EXISTING	PROPOSED
MIN. AISLE WIDTH FOR ONE-WAY 45° ANGLE PARKING (FT)	15	18±	15
MIN. AISLE WIDTH FOR TWO-WAY 90° ANGLE PARKING (FT)	24	24	24
MAX. AISLE WIDTH FOR TWO-WAY (FT)	24	25	24
MIN. PARKING SPACE WIDTH (FT)	8.5	8.5±	8.5
MIN. PARKING SPACE LENGTH (FT)	18	18±	18
HANDICAPPED PARKING PROVIDED	3	4	4
SCREENING FROM ADJACENT PROPERTIES	YES	YES	YES





SITE PLAN: PARKING




- 1 Proposed Building
FFE 218.5
- 2 Multi-Use Court
- 3 Patio
- 4 Open lawn
- 5 Play structures
- 6 Emergency Vehicular
access
- 7 Rain garden (add alternate)
- 8 Screen planting
- 9 Existing vegetation to
remain
- 10 Boardwalk crossing
- 11 Utility area
- 12 Leaching Field
- Approx Limit of Work


STORMWATER + SEPTIC INFILTRATION







BUILDING PERFORMANCE





EXTERIOR SHADING



NORTH PATIO





MAIN ENTRANCE





DISCUSSION